

ADDENDUM #1

September 9, 2026

Project: AIRFIELD RAMP REPAIR
JOE FOSS FIELD
SIOUX FALLS, SOUTH DAKOTA
OSE# N1827--114

Bid Opening: September 14, 2026
03:00pm CT

At: Office of the State Engineer
Joe Foss Building
523 East Capitol Avenue
Pierre, South Dakota 57501-3182

Owner: State of South Dakota, Dept of the Military, SDANG

Scope of this Addendum:

The following becomes a part of the original Project Manual, taking precedence over items that may conflict. The bidder shall note receipt and make acknowledgment of the addendum in their bid and incorporating its provisions in their bid price.

- Item No. 1 Any disturbed grass areas to the north of the work location do NOT need to be re-seeded. Only regraded to fill in any holes.
- Item No. 2 Work hours are 0700-1700 Monday through Friday, however longer hours could be allowed for certain portions of the work if coordinated in advance.
- Item No. 3 All personnel on site will have to pass a background check. A minimum of a 24-hour notice is required before attempting to access base.
- Item No. 4 All field inspections will be accomplished by Geotek working with the State Engineering office.
- Item No. 5 Compaction tests are only required for the top lift of engineered fill.
- Item No. 6 The intent is to have engineered fill for the entire 24" depth below the pavement.

Item No. 7 Reference pages 255-260 of the Front Ends for specific concrete requirements. This project does have a stronger compressive strength requirement than the generic spec outlined in section 380 of the SD DOT 2015 Spec Book

B. Parking Apron/Ramp/Taxiway: Proportion normal-weight concrete mix as follows:

1. Compressive Strength, when tested IAW ASTM C39/C39M-18 at 28 Days: 4,500 psi.
2. Fly Ash Content: Maximum 15 percent of cementitious materials by weight.
3. Total Air Content: 6.5 percent, $\pm 1.0\%$, as determined IAW ASTM C173/C173M-16.
4. Maximum Slump: ≤ 4 inches.

Item No. 8 There is no sheet C302 for pavement markings. Disregard that on the page index of the drawings.



STACY WATTERS, PE
State Engineer
Office of the State Engineer

